

# **Radiofrequency for ALBA-II**

P. Solans on behalf of ALBA-RF team (presented by F. Perez)

11/10/2022






- ALBA-II General Overview
- ALBA-II Radiofrequency system
  - Main system
  - 3<sup>rd</sup> harmonic system
    - SSPA transmitter
    - DLLRF
    - Cavity





#### Upgrade the 3rd Generation ALBA Storage Ring to a 4th Generation Ultra Low Emmittance Ring: ALBA II



with the aim of doing the it as efficiently as posible, in terms of cost and time.



#### **Optimization parameters**

- Keep beam energy 3 GeV
- Keep the tunnel → SR with similar compact circumference
- Keep existing ID beamlines → preserve 16 cells and source points
- Bending beamlines can be relocated
- Keep injector (present  $\varepsilon_x^{\text{booster}} = 10 \text{ nm} \cdot \text{rad}$ )
- Keep infrastructures, as much as possible
- Straight sections ~4 m, with  $\beta_x \sim \beta_y \sim$  2 m
- Reduce emittance by more than a factor 10 (<400pmrad)





#### From 2x8 double-bend lattice to 16 multi-bend lattice (6BA)





Figure 1: In ALBA-II, the two types of DBA cell (8 matching cells plus 8 unit cells) of the current lattice are replaced by 16 identical 6BA+anti-bend cells.

	Current DBA	6BA
Emittance	4.5 nm∙rad	140 pm∙rad
Energy	3 GeV	3 GeV
Circumference	268.8 m	268.8 m
N.of cells	8+8	16
N. of straights	4 / 12 / 8	16
Straight length	7.8 / 4 / 2.3 m	4.0 m
Straight ratio	36%	24%
Working point	18.15, 8.36	43.68, 11.67
Chromaticity	-39, -29	-94, -51
Mom.comp.fact.	8.9.10-4	0.8.10-4
Energy spread	1.0·10 <sup>-3</sup>	1.1·10 <sup>-3</sup>
Energy loss/turn	1023 keV	843 keV
Damping times	4 / 5 / 3 ms	3 / 6 / 6 ms


### ALBA-II straight sections for IDs








#### **ALBA-II** implementation





Possible long beamlines at BL02-ID, BL03-Bend, BL04-ID, BL08-ID




#### **ALBA-II** Implementation

- Magnets
  - ~ 600 magnets
  - With power supplies
  - Some, permanent magnets?
- Vacuum chambers
  - ~ 270 m vacuum chambers
  - SS, Cu, NEG coated
- Girders
  - High vibration modes
  - High precision remote movement
- Many others:
  - Upgrade RF system with SSPA and 3<sup>rd</sup> Harmonic Cavity
  - New Diagnostics equipment
  - New Insertion Devices
  - ...



#### **ALBA-II** Main System

- 500 MHz EU HOM cavities.
- IOT based transmitter replaced by SSPA.
- Main RF parameters:




	ALBA	ALBA-II
Average current	250 mA	300 mA
Harmonic number	448	448
Natural bunch duration	15.8 ps	5.5 ps
Main voltage	3 MV	2.4 MV
Number of main cavities	6	6
RF acceptance	2.75 %	8 %
Natural synchrotron frequency	8.5 kHz	2.5 kHz
Transmitter power	90 kW	82 kW
Synchronous phase	160 <u>Deg</u>	153 <u>Deg</u>

P<sub>c</sub> = 24.24 kW



#### **ALBA-II** Main System

- Novel Trip Compensation (TC)
  - Amplitude and phase response allows to decrease main RF voltage and still survive a cavity trip.
  - Secondary phase rotation to avoid oscillations.



No TC  $\rightarrow$  Beam lost


Phase TC  $\rightarrow$  large voltage oscillations

Phase & Amplitude TC  $\rightarrow$  more stable voltage




• A 3<sup>rd</sup> harmonic system is needed for lifetime improvement by means of bunch lengthening.

	ALBA-II
Number of harmonic cavities	4
Total harmonic voltage	700 kV
Coupling factor	0.4
Harmonic synchronous phase	-10 Deg
Harmonic transmitter power (300 mA)	5 kW / cavity
Beam power (300 mA)	-9 kW / cavity
Lengthening factor	4.4
Bunch duration	24.2 ps
Lifetime (transversal full coupling)	17.2 h



ALBA-II - HH RF cavity - Voltage phasor plot Im [V] -0.5 I<sub>sr</sub> 0.5 -1.5 -1 <10<sup>5</sup> Re [V] V\_ = 175 kV  $V_{b}^{c} = 33.7 \text{ kV}$  $V_{b}^{g} = 166.2 \text{ kV}$  $\psi_{d} = 69.4^{\circ}$  $\psi_{gr}^{d} = -99.7^{\circ}$  $\psi_{r}^{gr} = 0^{\circ}$  $V_{t} = 2.4 \text{ MV}$  $V_{t \text{ hhc}} = 700 \text{ kV}$  $\beta_{\text{hhc}} = 0.4$  $\beta_{\text{hhc opt}} = 0.36$  $U_{t} = 1.092 \text{ MeV}$  $m\phi_{s \text{ hhc}} = -9.71^{\circ}$ 1.5 -2  $\times 10^5$ 



 $P_g + P_b = P_c + P_r$ 

F. Pérez

10/10/22

11

www.albasynchrotron.es



- 1.5 GHz SSPA transmitter prototype.
  - Manufactured by COMMTIA Systems S.A., Spain.
  - Gallium Nitride transistor.
  - Individual circulator for every transistor.
  - FAT performed on 06/10 successfully.

Main frequency	1.5 GHz
Bandwidth	5 MHz
Total power	5.0 kW
Gain	> 65 dB
Transistor drain efficiency	72.0 %
Transmitter efficiency	52.0 %





- 1.5 GHz DLLRF prototype developed.
  - Struck Innovative Systeme (SIS):
    - uTCA.4
    - SIS8300KU
    - SIS8864
    - DWC8VM1
  - 10 ADC, 2 DAC + direct output modulator, 64 GPIO, 125 MHz clock rate, ...
  - Complete rack with LO generation crate, Plunger motor controller, GPIO patch panel, PSU, ...
  - Call for Tender published on 09/22 for main and harmonic DLLRF.





- Harmonic EU Cavity according to ALBA Active Design.
  - 2015: ALBA team started the design of an active 1.5 GHz normal conducting cavity for CLIC Damping Ring and ALBA 3rd Harmonic.



The **prototype design** was co-funded by ALBA and the CERN through the collaboration agreement KE2715/BE/CLIC for the Development of CLIC Damping Ring Technologies (2015-2018).

• 2018: ALBA, with EU funds, started the construction of a prototype.



The **prototype construction** was co-funded by ALBA and the European Regional Development Fund (ERDF) within the Framework of the Smart Growth Operative Programme 2014-2020.


• 2020: Agreement between ALBA, HZB and DESY for testing the cavity.



The **prototype tests** were co-funded by ALBA, HZB and DESY through the collaboration agreement RCN-CIN202100124 (2020-2023).




- Harmonic EU Cavity according to ALBA Active design.
  - Jul 2021: Elegant simulation started for ALBA-II
    - See I. Bellafont talk 11/10 3<sup>rd</sup> session.




HC Simulations for ALBA-II

- Dec 2021: SAT at ALBA facility.
  - See J. Ocampo talk 12/10 1<sup>st</sup> session.

- Sep 2022: Tested at Bessy II with beam.
  - See A. Matveenko talk 11/10 4<sup>th</sup> session.



ALBA 3HC design and construction




ALBA 3HC comissioning results

www.albasynchrotron.es



## Thanks!



16

www.albasynchrotron.es